WATER SUPPLY DIVISION, BANGALORE.

Dated 9th January 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Water Supply Division, up to 1st February 1932 at 2-30 P.M., for improving Water Supply to Kolar Town, constructing Filter and Alum-House. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1932.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Water Supply Division, between the hours of 11 A.M. to 5 P.M., on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 350 in cash or Government Promissory Notes as earnest money and be superscribed "Tender for improving Water Supply to Kolar Town," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8 On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer, Water Supply Division, will be final and legally binding.

Abstract estimate of quantities required for constructing Filter and Alum-House at Kolar close to the exising filter beds and service reservoir.

No.	Items of work	Unit	Rate Rs.	a.	p.	Quantity	Cost
1	Earthwork excavation and refilling basement including hard gravel and moorum.					53	
2	Burnt stone jelly concrete in chunam mortar ...	C.ft.				486	
3	Burnt stone in chunam mortar ...	,,				1,387	
4	Burnt brick in chunam mortar ...	,,				2,525	
5	Burnt stone slabs 4½″ thick two line nicely dressed and fixed on mortar bed and faces cut to square and projected ½″ beyond the walls.	S.ft.				280	
6	Burnt stone slabs 6″ thick one line dressed and fixed in mortar.	,,				50	
7	Chunam plastering ½″ thick	Sqr.				26·72	
8	Rough cast plastering with round jelly not more than ¼″ inches in cubes mixed with cement.	,,				13·00	
9	Archwork over ventilators constructed with burnt brick in mortar.	C.ft.				42	
10	Cutting quoins in pillasters at corners ...	Sqr.				3·20	
11	Teakwood panelled door 1 5/8″ thick plank and 5″ x 6″ frame with 6 iron hinges, etc., complete for one door.	S.ft.				64	
12	Teakwood shelves with 1″ thick planks and 2″ x 3″ wooden pegs inserted in the walls.	,,				12	
13	Teakwood windows 4″ x 4½″ frame, ½ panelled and ½ glazed with 1″ thick planks and ¾″ iron bars and iron fastenings, complete.	,,				264	
14	Teakwood semi-circular ventilators with glazed shutters frame 3″ x 4″ thick as per design in plan.	,,				16	

No.	Items of work	Unit	Rate			Quantity	Cost
			Rs.	a.	p.		
15	Teakwood wrought and put up with wood oiling	C.ft.				98	
16	Teakwood plain eave board 1″ x 9″ with painting	R.ft.				194	
17	Teakwood ornamental finials	No.				2	
18	Teakwood pendants	,,				8	
19	Burnt stone pillars 6″ x 6″ square two line dressed, edges chamfered with base and capital complete four of 8½′ long.	R.ft.				34	
20	Do do half pillars two of 8½′ long	,,				17	
21	Teakwood ornamental railings 2½ feet high with painting.	,,				22	
22	Cement pointing to basement (1 cement and 3 sand).	Sqr.				2 94	
23	Flooring with 3″ burnt stone slabs (two line dressed) on 3″ concrete bed and cement pointing.	,,				9·35	
24	Whitewashing two coats	,,				26·72	
25	Roofing with First Class Mangalore tiles on teak reepers 2″ x 1″ with wood oiling to reepers and constructing mortar bands on roof with plastering, etc., complete.	,,				17·12	
26	Ridge tiles set in mortar and cement pointed ...	R.ft.				64	
27	Painting two coats with silicate painting ...	Sqr.				9·50	
28	Wood oiling two coats	,,				1·00	
29	Fixing purlins of M. & S. M. rails in one length	R.ft.				36	
30	Ornamental borders in chunam alround doors and windows complete as per plan.	,,				268	
31	Iron trusses as per design including hoisting and fixing with painting.	No.				2	
31a	Rolled steel girders 12″ x 6″ and weighing 44 lbs. per foot including hoisting and fixing.	Cwt.				8½	
32	Ornamental cement work on doors and windows at top as per plan.	No.				12	
33	Forming 3″ drain in surki concrete and cement plastering with ½″ thick, complete.	R.ft.				30	
34	Constructing rough stone drain with available old stones 1 foot by 1 foot inside.	R.ft.				200	

H. F. MARKER,
Executive Engineer.

TUMKUR DIVISION.

Dated 8th January 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 5th February 1932, for constructing an Anicut across Jayamangali River near Kyamenahalli, Koratagere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the end of December 1933.

2. The plans, detailed estimates and the conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. and 5 P.M., on working days.

3. Tenders should be submitted on printed forms which may be obtained form the Executive Engineer. The tenders should be accompanied by statement in the form given below, showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of Rs. 1,000 in cash or currency note as earnest money and be superscribed "Tender for constructing an Anicut across the Jayamangali River near Kyamenahalli, Koratagere Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates and measurements quality of work, etc., and in all disputes of any kind, the decision of the Chief Engineer will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work and lump sum provisions are subject to modification as per data worked out during the execution. For individual item of work under lump sum provisions the rates tendered for similar items of work will be paid and for other items the rates as per schedule of rates will be paid at the descretion of the Executive Engineer.

Abstract estimate showing the quantities for constructing an anicut across Jayamangali near Kyamenahalli, Koratagere Taluk.

Sl. No.	Items of work	Unit	Quantity	Rate	
				In words	In figures
				Rs.	Rs.
1	Cutting jungle	Lump sum			
2	Earthwork excavation stony and hard soil ...	C.yd.	2,513		
3	Earthwork excavation fishared rock ..	,,	388		
4	Bailing water	Lump sum			
5	Concrete in surki mortar	C.ft.	3,510		
6	Burnt stone in surki mortar mixed masonry ...	,,	8,197		
7	Face stone two line dressed in surki mortar ...	,,	4,732		
8	Do in cement mortar	,,	1,430		
9	Burnt brick in surki mortar	,,	11,818		
10	Burnt stone slabs 6" thick roughly dressed and cement pointing.	S.ft.	692		
11	Cement pointing	Sqr.	16·90		
12	Plastering with surki mortar	,,	6·10		
13	Cutting groves in slabs providing joggle joints and cement pointing.	Each	26		
14	Rough stone big boulders and jelly packing three miles lead.	C.yd.	1,064		
15	Rough stone work new	,,	491		
16	Turfing	S.yd.	2,524		
17	Earthwork to flank bund with consolidation ...	C.yd.	2,488		
18	Construction of a new head sluice demolishing old anicut and blocking up old channel head, etc.	Lump sum			
19	Unforeseen charges	Lump sum			

A. TANDONI RAO,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

THE PALACE, MYSORE.

Memo, dated 6th January 1932.

Sealed tenders for the supply of horsegram to the Palace will be received by the undersigned on Friday the 29th January 1932. Particulars can be obtained from the Munib, Mo thikhana, Mysore.

M. RAMA RAO,
For *Huzur Secretary.*